Bruhath Bengalore mahanagara palike
Dasarahalli Zone

Name of Work: Development of Shettyhalli Burial Ground in S.No.55,56 and Deep land ward No12 C Category

Sl No	Description of work	Unit	No	Length m	Width m	Depth m	Quantity	Rate in Rs	Amount
	Civil Work								
1	KSRRB M200-11.1. **Clearing and grubbing road land** including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removalof stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, including removal and disposal of top organic soil not exceeding 150 mm in thickness complete as per specifications. II. By Mechanical Means B. In area of thorny jungle (P.No-137,I No-18.16)								
	Shettyhalli Burial Ground	Sqm	1	(146+120)/2	(60+46)/2	--	7049		
	Deduction for Voids						-2114.7		
							4934.3		
							0.49	26847.68	13247.45
	Basic Rate		25328.00						
	Add 6% AW		1519.68						
	Total Rate		26847.68						
2	KSRB 2-1 : Earthwork in surface excavation for levelling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications. KSRB 2-1.1: – do – Ordinary soil P NO-6, I NO-2.1								
	Shettyhalli Burial Ground	Cum	1	As per Volume Sheet			10965.21		
							10965.21	298.42	3272238.00
	Basic Rate		157.00						
	Add 6% AW		9.42						
	Loading and Unloading		68.00						
	Lead 20km		64.00						
	Total Rate		298.42						
3	KSRB 2-2 : Earthwork excavation by manual means for **foundation of buildings, water supply** and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications. (P.No-5,I No-2.3)								
	Shettyhalli Burial Ground	Cum							
	For Compound Wall		1	109.74	1.10	1.20	144.86		
	For Compound Coloumn		44	0.45	1.10	1.20	26.14		
	Entrance Arch Footing		2	1.80	1.80	1.50	9.72		
	Security Room		2	2.82	1.10	1.20	7.44		
			1	3.70	1.10	1.20	4.88		
	Gazebo		1	17.20	1.10	1.00	18.92		
	Gazebo Platform		2	2.45	1.10	1.00	5.39		
	Pipe Line		1	422.00	0.60	0.90	227.88		
	SWD Drain		1	104.00	(3.4+2.4)/2	1.50	452.40		
	Gym Equipments		13	0.60	0.60	0.70	3.28		
							900.91	**332.34**	**299407.63**
	Basic Rate		189.00						
	Add 6% AW		11.34						
	Loading and Unloading		68.00						
	Lead 20km		64.00						

Scanned by CamScanner

Sl No	Description of work	Unit	No	Length m	Width m	Depth m	Quantity	Rate in Rs	Amount
	Total Rate		332.34						
4	Earth work excavation for foundation of structures upto 3 mtrs. by mechanical means as per drawing and technical specification, including setting out, providing shoring, strutting and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, filling back the excavated earth to the extent required and utilising / transporting the remaining earth upto 1.00km lead. including cost of labour, materials and HOM etc., complete.- do Marshy soil. (P.No.8, I.No.2.23.4 of PW,P&IWTD S.R 2016-17)								
	Shettyhalli Burial Ground	**Cum**							
	SWD Drain		1	104.00	(2.4+2.3)/2	1.00	244.40		
							244.40	**400.18**	**97803.99**
	Basic Rate Rs.=		253.00						
	Add 6% A.W Rs. =		15.18						
	Loading and Unloading		68.00						
	Lead 20km		64.00						
	Total Rate Rs. =		400.18						
5	KSRB 2.8 : Providing and Filling in foundation with granite / **trap broken metal 100mm.** and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. (P.No-6,I No-2.15)								
	Shettyhalli Burial Ground	**Cum**							
	For Compound Wall		1	109.74	1.10	0.25	30.18		
	For Compound Coloumn		44	0.45	1.10	0.25	5.45		
	Entrance Arch Footing		2	1.80	1.80	0.25	1.62		
	Security Room		2	2.82	1.10	0.25	1.55		
			1	3.70	1.10	0.25	1.02		
	Gazebo		1	17.20	1.10	0.25	4.73		
	Gazebo Platform		2	2.45	1.10	0.25	1.35		
	SWD Drain		1	104.00	2.30	0.25	59.80		
							105.69	**2240.84**	**236833.26**
	Basic Rate		2114.00						
	Add 6% AW		126.84						
	Total Rate		2240.84						
6	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. P NO-7, I NO-2.11								
	Shettyhalli Burial Ground	**Cum**							
	Pipe Line		1	422.00	0.60	0.60	151.92		
	Gazebo Platform		1	1.45	0.56	0.50	0.41		
	Cobble Stone		1	(3.14*16.6*16.6)/4		0.20	43.26		
							195.59	**80.56**	**15756.64**
	Basic Rate		76.00						
	Add 6% AW		4.56						
	Total Rate		80.56						
7	KSRB 4-1.2 : Providing and laying in position plain **cement concrete of mix 1:3:6** with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No. 12/I.No. 4.2 of CSR 2016-17)								
	Shettyhalli Burial Ground	**Cum**							
	For Compound Wall		1	109.74	1.10	0.15	18.11		
	For Compound Coloumn		44	0.45	1.10	0.15	3.27		

Scanned by CamScanner

Sl No	Description of work	Unit	No	Length m	Width m	Depth m	Quantity	Rate in Rs	Amount
	Entrance Arch Footing		2	1.80	1.80	0.15	0.97		
	Security Room		2	2.82	1.10	0.15	0.93		
			1	3.70	1.10	0.15	0.61		
	Gazebo		1	17.20	1.10	0.15	2.84		
	Gazebo Platform		2	2.45	1.10	0.15	0.81		
	Security Room Flooring		1	3.70	2.80	0.15	1.55		
	Gazebo Flooring		1	5.20	5.20	0.15	4.06		
	Gazebo Platform		1	1.89	0.56	0.15	0.16		
	SWD Drain		1	104.00	2.30	0.15	35.88		
	Gym Equipments		13	0.60	0.60	0.15	0.70		
							69.88	**5348.76**	**373795.20**
	Basic Rate		5046.00						
	Add 6% AW		302.76						
	Total Rate		5348.76						
8	KSRB 5.2-3 : Providing and constructing granite / **trap / basalt size stone masonry** in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.(P.No-23,I No-5.6)								
	Shettyhalli Burial Ground	**Cum**							
	1st Step SSM Foundation								
	For Compound Wall		1	109.74	0.60	0.90	59.26		
	For Compound Coloumn		44	0.45	0.75	0.90	13.37		
	Security Room		2	2.82	0.60	0.90	3.05		
			1	3.70	0.60	0.90	2.00		
	2nd Step SSM Foundation								
	For Compound Wall		1	109.74	0.45	0.60	29.63		
	For Compound Coloumn		44	0.45	0.60	0.60	7.13		
	Security Room		2	2.82	0.45	0.60	1.52		
			1	3.70	0.45	0.60	1.00		
	Gazebo		1	17.20	0.45	0.60	4.64		
	Gazebo Platform		2	2.45	0.45	0.60	1.32		
							122.91	**4438.22**	**545522.92**
	Basic Rate		4187.00						
	Add 6% AW		251.22						
	Total Rate		4438.22						
9	KSRB 15.1.3 – do – Providing **ruled pointing t**o coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.(P.No-113,I No-15.3)								
	Shettyhalli Burial Ground	**Sqm**							
	2nd Step SSM Foundation								
	For Compound Wall		1	109.74	--	0.60	65.84		
	For Compound Coloumn		44	0.45	--	0.60	11.88		
	Security Room		2	2.82	--	0.60	3.38		
			1	3.70	--	0.60	2.22		
	Gazebo		1	17.20	--	0.60	10.32		
	Gazebo Platform		2	2.45	--	0.60	2.94		
							96.59	**103.88**	**10033.5**
	Basic Rate		98.00						
	Add 6% AW		5.88						
	Total Rate		103.88						

Scanned by CamScanner

Sl No	Description of work	Unit	No	Length m	Width m	Depth m	Quantity	Rate in Rs	Amount
10	KSRB 4-6.1 : Providing and **removing centering, shuttering, strutting,** propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. (P.No-15,I No-4.31)								
	Shettyhalli Burial Ground	**Sqm**							
	Compound Wall Plinth band		2	109.74	--	0.20	43.90		
	For Compound Coloumn		88	0.45	--	0.20	7.92		
	Entrance Arch Footing		2	6.00	--	0.45	5.40		
	Entrance Arch Coloumn Upto Plinth		2	2.60	--	0.70	3.64		
	Entrance Arch Coloumn above Plinth		2	2.60	--	3.27	17.00		
	Entrance Arch Top Beam		1	7.40	--	2.40	17.76		
	Security Room		4	2.82	--	0.20	2.26		
			2	3.70	--	0.20	1.48		
	Gazebo		2	17.20	--	0.20	6.88		
	Gazebo Platform		4	2.45	--	0.20	1.96		
	For SWD Bottom Slab		1	104.00	--	0.20	20.80		
	SWD Side Wall		4	104.00	--	1.50	624.00		
							753.00	**310.58**	**233865.50**
	Basic Rate		293.00						
	Add 6% AW		17.58						
	Total Rate		310.58						
11	KSRB 4-6.3 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per Specification. Specification. P NO-15 I NO-4.30								
	Shettyhalli Burial Ground	**Sqm**							
	For Top Slab		1	79.50	1.90	--	151.05		
							151.05	**407.04**	**61483.39**
	Basic Rate		384.00						
	Add 6% AW		23.04						
	Total Rate		407.04						
12	KSRB 4.2.1 : Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification. P NO-13, I NO-4.10								
	Shettyhalli Burial Ground	**Cum**							
	For SWD Bottom Slab		1	104.00	1.90	0.20	39.52		
	SWD Side Wall		2	104.00	0.20	1.50	31.20		
	For Top Slab		1	79.50	1.90	0.25	37.76		
							108.48	**6371.66**	**691213.61**
	Basic Rate		6011.00						
	Add 6% AW		360.66						
	Total Rate		6371.66						

Scanned by CamScanner

Sl No	Description of work	Unit	No	Length m	Width m	Depth m	Quantity	Rate in Rs	Amount
13	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of **Design mix M20** with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. (P.No-13,I No-4.11)								
	Shettyhalli Burial Ground	Cum							
	Plinth for Compound Wall		1	109.74	0.45	0.15	7.41		
	For Compound Coloumn		44	0.45	0.60	0.15	1.78		
	Entrance Arch Footing		2	1.50	1.50	0.50	2.25		
	Entrance Arch Coloumn Upto Plinth		2	0.65	0.65	0.70	0.59		
	Entrance Arch Coloumn above Plinth		2	0.65	0.65	3.27	2.76		
	Entrance Arch Top Beam		1	7.40	0.65	0.65	3.13		
	Security Room		2	2.82	0.45	0.15	0.38		
			1	3.70	0.45	0.15	0.25		
	Gazebo		1	17.20	0.45	0.15	1.16		
	Gazebo Platform		2	2.45	0.45	0.15	0.33		
	Security Room Flooring		1	3.70	2.80	0.15	1.55		
	Gazebo Flooring		1	2(1+√2)2.3*2.3		0.15	3.83	Octagon	2(1+√2)S*S
	Gazebo Platform		1	1.89	0.56	0.15	0.16		
	Gym Equipments		13	0.60	0.60	0.55	2.57		
							28.16	**6371.66**	**179429.51**
	Basic Rate		6011.00						
	Add 6% AW		360.66						
	Total Rate		6371.66						
14	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 TMT bars Fe 500 (P.No.17, I.No.4.46.2 of PW, P&IWTD SR 2016-17)								
	Shettyhalli Burial Ground	Tn							
	Considering steel @100 kg/ cum (front arch)		1	3.13	0.10	--	0.31		
	Consider Steel @85 kg/ Cum (For Plinth Concrete)		1	11.31	0.09	--	0.96		
	Consider Steel @35 kg/ Cum (For Column Concrete)		1	3.35	0.035	--	0.12		
	Consider Steel @80 kg/ Cum (For Footing Concrete)		1	2.25	0.08	--	0.18		
	Consider 120 kg/Cum (For Drain)		1	108.48	0.12	--	13.02		
							14.59	**64243.42**	**937298.84**
	Basic Rate		60607.00						
	Add 6% AW		3636.42						
	Total Rate		64243.42						

Scanned by CamScanner

No	Description of Work	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
				m	m	m		in Rs	
15	KSRB 5-11 : Providing and constructing load bearing wall with **solid concrete blocks of size 400x200x200** mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications (P.No-25,I No-5.27.1)								
	Shettyhalli Burial Ground	**Sqm**							
	for Compound Wall		1	109.74	--	2.20	241.43		
	For Compound Coloumn		88	0.45	--	2.20	87.12		
	Security Room		2	2.82	--	2.20	12.41		
			1	3.70	--	2.20	8.14		
	Gazebo		2	17.20	--	0.60	20.64		
	Gazebo Platform		2	2.45	--	0.60	2.94		
	Deduct for windows & doors								
	Windows		-1	1.25	--	0.89	-1.11		
	doors		-1	1.90	--	0.89	-1.69		
							369.87	**993.22**	**367364.76**
	Basic Rate		937.00						
	Add 6% AW		56.22						
	Total Rate		993.22						
16	KSRB 4-1.6 ; Providing and laying in position plain **cement concrete of mix 1:2:4** with cement @ 240kgs. with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications (P.No-12,I No-4.6)								
	Shettyhalli Burial Ground	**Cum**							
	Coping for Compound Wall		1	109.74	0.20	0.10	2.19		
	For Compound Coloumn		44	0.45	0.45	0.10	0.89		
	Security Room		2	2.82	0.20	0.10	0.11		
			1	3.70	0.20	0.10	0.07		
	Gazebo		1	17.20	0.45	0.10	0.77		
							4.05	**5767.46**	**23338.60**
	Basic Rate		5441.00						
	Add 6% AW		326.46						
	Total Rate		5767.46						
17	KSRB15-3.11 : Providing **20mm thick cement plaster** in single coat with cement mortar 1:4, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (P.No-114,I No-15.19)								
	Shettyhalli Burial Ground	**Sqm**							
	for Compound Wall		2	109.74	--	2.40	526.75		
	For Compound Coloumn		88	0.60	--	2.40	126.72		
	Security Room		4	2.82	--	2.40	27.07		
			2	3.70	--	2.40	17.76		
	Gazebo		2	17.20	--	0.85	29.24		
	Gazebo Platform		2	2.45	--	0.60	2.94		
	Entrance Arch Coloumn above Plinth		2	2.60	--	3.27	17.00		
	Entrance Arch Top Beam		1	7.40	--	2.40	17.76		
							765.25	**248.04**	**189812.11**
	Basic Rate		234.00						
	Add 6% AW		14.04						
	Total Rate		248.04						

Scanned by CamScanner

Sl No	Description of work	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
				m	m	m		in Rs	
18	KSRB 15-16.1 : Providing and finishing **external walls in two coats** with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer. (P.No-118,I No-15.53.2)								
	Shettyhalli Burial Ground	**Sqm**							
	for Compound Wall		2	109.74	--	2.40	526.75		
	For Compound Coloumn		88	0.60	--	2.40	126.72		
	Security Room		4	2.82	--	2.40	27.07		
			2	3.70	--	2.40	17.76		
	Gazebo		2	17.20	--	0.85	29.24		
	Gazebo Platform		2	2.45	--	0.60	2.94		
	Entrance Arch Coloumn above Plinth		2	2.60	--	3.27	17.00		
	Entrance Arch Top Beam		1	7.40	--	2.40	17.76		
							765.25	**89.04**	**68137.68**
	Basic Rate		84.00						
	Add 6% AW		5.04						
	Total Rate		89.04						
19	Providing and fixing **M.S. Gate as per Chief Architect Drawing,** using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members asshown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specifiocation. (P. No. 43 / I. No. 7.37 of CSR 2016-17)								
	Shettyhalli Burial Ground	**Sqm**							
	South Side Gate		1	6.70	--	2.74	18.36		
							18.36	**3110.04**	**57094.11**
	Basic Rate		2934.00						
	Add AW 6%		176.04						
	Sub Total		3110.04						
20	Fabricating, **providing and erecting in position Hot dip galvanised Gate.** Using 72 X 72 X 4.8mm Sq. GI Pipe Frame with Top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanised sq. rod for verticals at 150mm c/c, as shown in the drawing including providing hot dip galvanised forged ornamental design in between sq. rods and heads at top, middle and bottom. Intermediate supports of 75X12 mm and 50X6 mm arch bend to hot dip galvanised flats. The work is inclusive of throughing GI flat GI sq. rods, placing, welding all the joints including grinding, finishing metal putty, painting two coats enamel painting. The rate is inclusive of all materials like GI sq. pipe, GI sq. rods, GI forged designs etc., heavy duty hinges are made out of 75mm solid sq. block assembled with 20mm dia bearing in three places for each flop. Heavy Duty Locking arrangements at tow places including cost of labour, painting, erecting charges using hoist pulley cranes with all lead and lift, loading, transportation, unloading, scaffolding charges and all other incidental charges for successful completion of the work as per directions of the Engineer-in-charge of the work. (Data Rate)								
	Shettyhalli Burial Ground	**Sqm**							
	West Side Gate (Main Gate)		1	6.10	--	2.56	15.62		
							15.62	**12475.03**	**194810.07**

Scanned by CamScanner

Sl No	Description of work	Unit	No	Length m	Width m	Depth m	Quantity	Rate in Rs	Amount
25	Fabricating supplying and erecting M.S. TubulerTruss of all span as per approved drawing design with prefabricated applications using quality material and are durable reliable and corrosion and abrasion resistant. welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design gauge and polish. The entire trusses is anchored in RCC column by using 4 nos of M.S. anchor bolts at each support with 10mm thick base plate and shoe plate. The work includes cutting, straightening, placing in position of M.S. pipes and welding wherever necessary and applying one coat of redoxide primer coat to all the members including cost of all materials, labour charges of machineries for cutting, welding, grinding and erection equipments, with alllead and lift, transportation, etc, complete as per specification. (P.No.40, I.No.7.29 of PW.P&IWTD S.R 2016-17)								
	Gazebo Platform Roof	Sqm	1	2(1+√2)2.5*2.5		--	30.00		
	Consider 33kg per Sqm	Kg		33.00		--	990.00		
	Gazebo Platform Columns	Kg	8	2.05	6.51	--	106.76		
		Kg					**1096.76**	**118.80**	**130295.56**
	Basic		110.00						
	Add 8% A.W		8.80						
	Total Rate		118.80						
26	Supplying and fixing new Mangalore tiles on existing reepers. (P.No.256, I.No.37.9 of PWD SR 2016-17)								
	Gazebo Roof	**Sqm**	2	2(1+√2)3*3		--	86.92		
	Basic		363.00				**86.92**	**392.04**	**34076.12**
	Add 8% A.W		29.04						
	Total Rate		392.04						
27	Providing Mangalore Ridge tiles set in C.M. 1:2 and pointed with C.M. 1:2. (P.No.255, I.No.37.7 of PWD SR 2016-17)								
	Gazebo Roof	**m**	16	3.00	--	--	48.00		
	Basic		176.00				**48.00**	**190.08**	**9123.84**
	Add 8% A.W		14.08						
	Total Rate		190.08						
28	Providing corrugated cement asbestos Ridge sheets set in C.M. 1:3 and pointed with C.M. 1:3. including cost of materials, labour, HOM complete as per specifications. P No-266, I No-37.6 KPWD SR 2016-17.								
	Security Room Roof	**m**	6	4.00	--	--	24.00		
	Basic		436.00				**24.00**	**470.88**	**11301.12**
	Add 8% A.W		34.88						
	Total Rate		470.88						
	Bore Well								
9	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction (P.42, I. 9.4) PRED.SR 2012-2013								
		Nos	1	--	--	--	1	1938.46	1938.46

Scanned by CamScanner

Sl No	Description of work	Unit	No	Length m	Width m	Depth m	Quantity	Rate in Rs	Amount
30	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding cost of casing pipes, collars, cap etc..) **Page no. 41 / I No. 9.1 PRED SR 2012-2013**								
	Upto 50.00 m depth	m	1	50.00	--	--	50.00	315.18	15759.00
	Above 50.00 to 100.00 m	m	1	50.00	--	--	50.00	412.00	20600.00
	Above 100.00 to 150.00 m	m	1	50.00	--	--	50.00	458.35	22917.50
	Above 150.00 to 200.00 m	m	1	50.00	--	--	50.00	484.10	24205.00
	Above 200.00 to 250.00 m	m	1	50.00	--	--	50.00	560.32	28016.00
	Above 250.00 to 300.00 m	m	1	50.00	--	--	50.00	600.49	30024.50
	Above 300.00 to 350.00 m	m	1	50.00	--	--	50.00	640.66	32033.00
31	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket confirming to IS 4270 : 2001 and other end with Screwed pipes. All pipes shall be resonably free from defects. The tube shall be resonably stright should be with ISI marking, weighing 25.10 kg/m (inclusive of all taxes and durties). Prices include Collar-medium duty material Component (P.No-iii, I No-84) of PRED SR 2012-2013.	m	1	44.00	--	--	44.00	1325.00	58300.00
32	Providing 175mm dia ms collar (P No-iii, I No-86) PRED SR 2012-2013	Nos	1	2.00	--	--	2.00	150.00	300.00
33	Providing 175mm dia bore cap CE(M) page no III it no 56 PRED 2012-2013	Nos	1	1.00	--	--	1.00	100.00	100.00
34	Supplying PVC pipes 100kg/Sqm 250mm Dia PVC (casing pipe) (P No-XXXi, I NO-909) PRED SR 2012-2013	Nos	1	50.00	--	--	50.00	2600.00	130000.00
35	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM and testing complete as per specifications. Specification No.KBS 13.2.14 / 13.6 (P. No.92/ I. No. 13.15 KPWD SR 2016-17	m	1	320.00	--	--	320.00	457.92	146534.40
36	Supply and delivery at site brand Atalanbta, Suguna, CRI Kirloskar and other equipment pumps 10.00 HO/7.5KV 920 Stages) (Page No-XXXX, I NO-21) KPWD SR 2016-17	Nos	1	1.00	--	--	1.00	50100.00	50100.00
7	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of Group-A **P. No. 12/ I No. (2.10.3)KPWD Electrical SR 2014-15 3CX-4.0 sqm**	m	1	360.00	--	--	360.00	126.70	45612.00
	Providing and fixingin position 50mm nominal bore non-returnable valve vertical type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification NO.KBS 13.2.10/13.13 (Page No- 93, I No-13.62) KPWD SR 2016-17.	Nos	1	1	--	--	1.00	1521.10	1521.10
	Supplying and fixing 50mm GI Union (Page No-XXXVII) KPWD SR 2016-17	Nos	1		--	--	1.00	223.70	223.70
	Supplying and fixing 50mm GI Elbow (Page No-XXXVII) KPWD SR 2016-17								

Scanned by CamScanner

Sl No	Description of work	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
				m	m	m		in Rs	
53	Supplying and fixing wiring, earth electrode for grounding conduits IC Cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI Pipe 2.5 Mtr long buried in a pit..... The pit should be filled with equal proportion of salt and charocoal 150mm alround the pipe to complete depth. The connections from the pipe to the conduit etc. is to be established though GI Wire of size as per ISI Specification 7.3.3 of IS 732 using 12mm dia bolts, nuts, washers and checknuts etc. the pipe shall have 16 through holes of 122 mm dia. (PWD Ele SR 2014-15, P No-62, I No-7.1)								
		Nos	1				1.00	2727.00	2727.00
54	Supplying and fixing Class-A (Medium duty) -GI pipe wall thickness not less than 3.25mm on pole/wall/Drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm (PWD Ele SR 2014-15, P No-68, I No-7.12.3)								
		m	1	5.00	--	--	5.00	345.00	1725.00
55	Supplying laying of 1.1 KV class L.T.U.G Cable having aluminium conductor PVC insulated extruded inner shethed galvanised steel strip (except 2C x 10 Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with speicified IS-1554, Part-1:1988 & confirming to the attached GTP of Group A 4 core to 16Sqmm (PWD Ele SR 2014-15, P.No.62, I No- 7.4.5)								
		m	1	40.00	--	--	40.00	140.40	5616.00
56	Labour charge for laying of 1.1 KV class UG cablein existing trench GI pipe / stoneeware pipe / on wall / o pole as required. IN existing trench // duct . 6sqmm to 16sqmm (Page No.61, Sl No 7.8.1) PWD Electrical SR 2014-15								
		Nos	1	50.00	--	--	50.00	10.80	540.00
57	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating in Hard soil etc., complete.(PWD Electrical SR 2014-15, P-68, It-7.9.2)								
		Nos	1	50.00	--	--	50.00	106.00	5300.00
58	Supplying and fixing LT cast iron pot heads suitable for 1.1 KV class UG cable filled wiith necessary bitumen / insulating compound complete. With terminals, clamps, bolts nuts and washers etc.complete for 16 Sqmm as per specification (PWD Ele SR 2014-15, P No-69, I No-7.13.2)								
		Nos	1	--	--	--	1.00	280.00	280.00
59	KSRB 14.6-1: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS. (P.No. 101, I.No. 14.6 of CSR 2015-16)								
	Shettyhalli Burial Ground								
	Abbigere Park	**Sqm**	1	(3.14*16.6*16.6)/4				**216.31**	**966.72**	**209115.65**
	Basic		912.00						
	Add 6% A.W		54.72						
	Total Rate		966.72						
60	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete								
	Shettyhalli Burial Ground	**Nos**							
	Abbigere Park	**m**	1	52.10	--	--	52.10		
							116.00	**331.78**	**3848**
	Basic		313.00						
	Add 6% A.W		18.78						

Scanned by CamScanner

Sl No	Description of work	Unit	No	Length m	Width m	Depth m	Quantity	Rate in Rs	Amount
64	**Supply & fixing of Self Weighted Rower** : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. The seat and backrest is made from Rotomoulded LLDPE. Bearings : Maintenance-free ball bearings. Equipment which have sway and moving parts, must have built in limitors that prevent unwanted and ecesssive movement, which can cause injuries. The limitors must be in accordance with EN16630 safety norms. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 1390 MM x 805 MM x 1198 MM . Capacity 1 person. Inclusive of All Taxes and Transportation Charges (Data approved rate)								
	Shettyhalli Burial Ground								
	Abbigere Park	**Nos**	1	--	--	--	1.00	**206250.00**	**206250.00**
	Data Rate		206250.00						
65	**Supply & fixing of HD Health Walker** :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Footplates made of alloys of Nylon having good thermal stability. Internal Limited means no bump stops or crush points. Bearings : Maintenance-free ball bearings. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 1070 MM x 615 MM x 1360 MM . Capacity 1 person. Inclusive of All Taxes and Transportation Charges								
	Shettyhalli Burial Ground	**Nos**							
	Abbigere Park		1	--	--	--	**1.00**	**175000.00**	**175000.00**
	Data Rate		175000.00						
66	**Fixing and installation of a three person body twister station**: Size -131 X 100 X 133CM, that consists of three swivel stands that rotates but with a built in safety limitor that meets international safety standards as the arms and shoulders of the user are held square in the overhead hold that is fixed to a monolithic large arc tube center pillar without convex sides & minimal deformation ergonomically curved. The Center pillar has an OD of 89 mm, the wall thickness is min 3 mm & has a 8mm thick, 40cm gusset support at standard height of 1.4m. All fasteners to be of 304 stainless, Torx Anti Vandal Fasteners, All nuts enclosed in Polyamide Anti Vandal Caps. Finishing to be Metalized / Plasma zinc injection + Dupont/Alexta outdoor use color powder electrostatic coating. Safe Zone : 430 X 400 CM. Inclusive of All Taxes and Transportation Charges (Data approved rate)								
	Shettyhalli Burial Ground	**Nos**							
	Abbigere Park		1	--	--	--	1.00	**234574.00**	**234574.00**

Scanned by CamScanner

No				Width	Depth	Quantity	Rate	Amount
	Data Rate	234574.00	m	m	m		in Rs	

67 **Supply & fixing of Leg Stretch** : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Bearings : Maintenance-free ball bearings. Equipment which have sway and moving parts, must have built in limitors that prevent unwanted and ecesssive movement, which can cause injuries. The limitors must be in accordance with EN16630 safety norms. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 935 MM x 810 MM x 1135 MM . Capacity 3 persons. Inclusive of All Taxes and Transportation Charges

Shettyhalli Burial Ground	**Nos**							
Abbigere Park		1	--	--	--	1.00	**48800.00**	**48800.00**
Data Rate		48800.00						

68 **Supply & fixing of Rider** : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. The seat is made from Rotomoulded LLDPE. Bearings : Maintenance-free ball bearings. Equipment which have sway and moving parts, must have built in limitors that prevent unwanted and ecesssive movement, which can cause injuries. The limitors must be in accordance with EN16630 safety norms. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 910 MM x 655 MM x 1210 MM . Capacity 1 person. Inclusive of All Taxes and Transportation Charges

Shettyhalli Burial Ground	**Nos**							
Abbigere Park		2	--	--	--	2.00	**112500.00**	**225000.00**
Data Rate		112500.00						

Scanned by CamScanner

No	Description of work	Unit	No	Length m	Width m	Depth m	Quantity	Rate in Rs	Amount
	Supply & fixing of HD Squat Pushing : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified international Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. The seat and backrest is made from Rotomoulded LLDPE. Bearings : Maintenance-free ball bearings. Equipment which have sway and moving parts, must have built in limitors that prevent unwanted and ecesssive movement, which can cause injuries. The limitors must be in accordance with EN16630 safety norms. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 2270 MM x 635 MM x 1640 MM . Capacity 2 persons. Inclusive of All Taxes and Transportation Charges								
	Shettyhalli Burial Ground	**Nos**							
	Abbigere Park		1	--	--	--	1.00	**268750.00**	**268750.00**
	Data Rate		268750.00						
70	**Fixing and Installation of a 2 person air skier machine** : Size - 113 X 50 X 133 CM, that consists of 2 arms with high grade fullfoot moulded foot rests made of high grade LLDPE which is attached to a monolithic large arc tube central pillar without convex sides & minimal deformation which are ergonomically curved to provide a pleasing aesthetic look with an OD of 89 mm, the wall thickness is min 3 mm & has a 8mm thick, 40cm gusset support. The arms are limited in movement as per international safety norms by the use of safe stopper [limiter]. All fasteners to be of 304 stainless, Torx Anti Vandal Fasteners, All nuts enclosed in Polyamide Anti Vandal Caps. Finishing to be Metalized / Plasma zinc injection + Dupont/Alexta outdoor use color powder electrostatic coating. Safe Zone : 410 X 350 CM. Inclusive of All Taxes and Transportation Charges								
	Shettyhalli Burial Ground	**Nos**							
	Abbigere Park		1	--	--	--	1.00	**244362.00**	**244362.00**
	Data Rate		244362.00						
71	**Fixing and Installation of a Leg Curl & Extension Machine**: Size - 91 X 40 X 133 CM, that contains a leg extension/curl dual action section that is affixed to the main monolitic curved arc tube central pillar without any convex sides of 89mm OD and min wall thickness of 3 mm & has a 8mm thick, 40cm gusset support using a ONE A.R.M MODULE (Angular resistance, bearing less module) that works as dual action [push and pull / extension & contraction]. The ARM must be bearing less, shock less, drop less and provide 0-30 kg resistance. The seats are fixed to the main curved central pillar and do not move up and down - [Are immovable] to ensure it is safe & stable, zero drops and support disable people to use the product without risk of falling or slipping off. All fasteners to be of 304 stainless, Torx Anti Vandal Fasteners, All nuts enclosed in Polyamide Anti Vandal Caps. The seat must consist of PU Polysafe cusions seats. Finishing to be Metalized / Plasma zinc injection + Dupont/Alexta outdoor use color powder electrostatic coating. Safe Zone : 390 X 340 CM. Inclusive of All Taxes and Transportation Charges								
	Shettyhalli Burial Ground	**Nos**							
	Abbigere Park		1	--	--	--	1.00	**287175.00**	**287175.00**

Scanned by CamScanner

Sl No	Description of work	Unit	No	Length m	Width m	Depth m	Quantity	Rate in Rs	Amount
	Data Rate		287175.00						
72	**Fixing and Installation of an Aero Walker** Size - 144 X 50 X 133 CM, that consists of 2 arms with high grade fullfoot moulded foot rests made of high grade LLDPE which is attached to two central pillars which are ergonomically curved monolithic arc tubes iwth minimal deformation to provide a pleasing aesthetic look with an OD of 89 mm, the wall thickness is min 3 mm & has a 8mm thick 40cm gusset support. The arms are limited in movement as per international safety norms by the use of safe stopper [limiter]. The systems has 3mm Endu-Rubber handles with aluminum cap locking anti vandal system. All fasteners to be of 304 stainless, Torx Anti Vandal Fasteners, All nuts enclosed in Polyamide Anti Vandal Caps. Finishing to be Metalized / Plasma zinc injection + Dupont/Alexta outdoor use color powder electrostatic coating. Safe Zone : 450 X 350 CM. Inclusive of All Taxes and Transportation Charges								
	Shettyhalli Burial Ground	**Nos**							
	Abbigere Park		1				1.00	**251349.00**	**251349.00**
	Data Rate		251349.00						
73	Supply & fixing of Pull Down Challenger : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. The seat and backrest is made from Rotomoulded LLDPE. Bearings : Maintenance-free ball bearings. Equipment which have sway and moving parts, must have built in limitors that prevent unwanted and ecesssive movement, which can cause injuries. The limitors must be in accordance with EN16630 safety norms. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 2570 MM x 840 MM x 2200 MM . Capacity 2 persons. Inclusive of All Taxes and Transportation Charges								
	Shettyhalli Burial Ground	**Nos**							
	Abbigere Park		1	--	--	--	1.00	**296000.00**	**296000.00**
	Data Rate		296000.00						
74	Supplying and fixing Porcelain fuse channel with cut out on the existing wooden / panel using necessary nuts , bolrs and washers. 63 Amps (PWD Ele SR 2014-15, P No-52, I No-6.7.3)								

Scanned by CamScanner

Sl No	Description of work	Unit	No	Length m	Breadth m	Depth m	Quantity	Rate in Rs	Amount in Rs
71	BESCOM Deposit charges and miscellaneous	Nos	1	4.00	--	--	4.00	234.00	936.00
		Nos	3	--	--	--	3.00	15000.00	45000.00
								Total Construction Cost	12004433.00
								KRIDL Charges	1320487.63
								PMC Cost	120044.33
99	Miscellaneous & Rounding							Sub Total	13444964.96
									5035.04
				Grand Total Rs.					13450000.00

Assistant Engineer | Assistant Executive Engineer | Executive Engineer

ನಂ: ಬಿಬಿಎಂಪಿ/ಕಾಸ/01/18-19 ದಿನಾಂಕ: 03/08/2018
ರೂ: Rs 134.50 LAKHS
.....
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.

ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಯೋಜನಾ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬಿಬಿಎಂಪಿ.

ನಂ. CE/TS/12/18-19 ದಿನಾಂಕ : 10/08/2018
ರೂ. ಸು. 134.50 Lakh ರೂಪಾಯಿ
.....
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.

ತಾಂತ್ರಿಕ ಸಹಾಯಕರು
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಜಿ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Scanned by CamScanner